

**ITEM 05-22: REPLACEMENT OF INBOUND SCALE AT THE AMSTERDAM TRANSFER STATION  
MONTGOMERY COUNTY  
DATED: APRIL 28, 2022  
BID ADVERTISEMENT MAY 2,2022  
BID OPENING MAY 24,2022 10:00 AM**

It is the intent of these specifications to solicit a unit price bid for the furnishing of all labor, equipment, and material necessary to replace the inbound 135 ton truck scale at the Amsterdam Transfer Station.

The successful Bidder is required to clean up, dispose of any surplus material, and restore any disturbed areas unless otherwise directed. Leave all areas clean!

The successful Bidder's attention is directed to the fact that all applicable State Laws, Federal Laws, Municipal Ordinances, and rules and regulations of authorities having jurisdiction over the project shall apply to the successful bidder throughout. They will be deemed to be included in the Bid Specifications the same as though herein written out in full.

When, in the opinion of the Montgomery County Treasurer and/or Designee, the successful bidder has satisfactorily completed the work at the given location, he/she will recommend the acceptance of the work completed. Once the County Treasurer and/or Designee accepts the work, the successful Bidder will be notified of such acceptance and the successful Bidder's Request for Payment will then be approved and submitted for payment.

Payment will be made at the price agreed upon in the bid award.

**INSURANCE:**

Before the actual commencement of work, the Contractor shall file with the County liability insurance policies, with limits not less than the following amounts indicated:

TYPES OF POLICIES

- a. Contractor's Liability Insurance
- b. Contractor's Protective Liability Insurance
- c. Completed Operations Liability Insurance
- d. Protective Liability Insurance for the County
- e. Owner, Landlords and Tenants Liability Insurance

Minimum Limits

<u>General Liability</u>		<u>Umbrella Liability</u>	
<u>Each Occurrence</u>	<u>Annual Aggregate</u>	<u>Each Occurrence</u>	<u>Annual Aggregate</u>
\$1,000,000.00	\$3,000,000.00	\$5,000,000.00	\$5,000,000.00

**AWARD OF BID**

Award of bid will be made to the lowest responsible bidder. The county reserves the right to reject any or all proposals, waive minor informalities and advertise for new proposals if in the best interests of the County.

**PREVAILING RATES SCHEDULE**

Successful contractor shall pay not less than the prevailing wage rate established by the New York State Department of Labor, Bureau of Public Works. The Wage Rate Schedule as prepared by the Department of Labor hereby becomes a part of the contract and is included herein.

The County of Montgomery reserves the right to extend any contract issued, based on this specification, under the same terms and conditions for a one year period from date of expiration, provided such extension is mutually agreeable to both County and Contractor.

**PROPOSAL FORM ITEM 05-22**  
**REPLACEMENT OF INBOUND SCALE AT THE AMSTERDAM TRANSFER STATION**  
**MONTGOMERY COUNTY**  
**Sheet 1 of 1**

Deliver Proposals to: Montgomery County Purchasing Agent  
PO Box 1500  
Fonda, NY 12068

The undersigned has read and understands the information and instructions to bidders and the specifications for the furnishing of Item 05-22 REPLACEMENT OF INBOUND SCALE AT THE AMSTERDAM TRANSFER STATION, Montgomery County, and proposes to furnish and deliver the item at the cost shown below:

PRICE BID \$ \_\_\_\_\_ UNIT AND INSTALLATION

FIRM NAME: \_\_\_\_\_

ADDRESS: \_\_\_\_\_

TELEPHONE: \_\_\_\_\_

SIGNATURE OF AUTHORIZED REPRESENTATIVE: \_\_\_\_\_

TYPED COPY OF ABOVE SIGNATURE: \_\_\_\_\_

TITLE: \_\_\_\_\_

DATE: \_\_\_\_\_

BIDDERS FEDERAL I.D. NO. OR SOCIAL SECURITY NO. \_\_\_\_\_

IS FIRM INCORPORATED? \_\_\_\_\_

IS FIRM MBE / WBE / VETERAN OWNED? \_\_\_\_\_

## EQUIPMENT SPECIFICATION

---

### 135 ton Truck Scale

#### SECTION A- SCALE

70x11-135T Low-Profile Motor Truck Scale - Checkered Steel Deck-suited for both above ground and pit

Capacity:	135 Tons
Platform Size:	70' x 11'
Platform Material:	1/4" Checkered Steel Deck Plate
Module Sizes:	(3) 23' x 11'
Concentrated Load Capacity(CLC)	45 Tons
Dual Tandem Axle Rating (DTA)	90,000#
"r" Factor	2.65
Weigh-Bridge Thickness	10-1/4"
Standard Profile ( <i>top of pier to top of approach</i> )	21"

#### WEIGH-BRIDGE COMPONENTS

- 1/4" checkered steel top plate
  - (13) 10" I-Beams
  - Continuously welded bottom steel plates
  - Continuously welded seam around perimeter
  - Heavy gauge steel end-plate sections
- 
- **Full 12-Year factory warranty on the weighbridge structure**
  - Easy top access to Weigh Bars and junction boxes
  - Superior weighbridge design
  - Internal self-checking, no external check rods
  - Full electronic design
  - Conduit runs and rodent barriers for cabling
  - 100% -construction in the USA
  - NIST and NTEP approval
  - Self-contained steel modules
- 
- Factory assembled, no field welding
  - "r" Factor- 2.65
  - Surge voltage- standard
  - 21" from pier to top of approach (*convenient base plate riser options for other elevations*)
  - Lightning protection- standard for scale peripherals