

RFP: 14-22

RFP- Demolition and replacement of concrete floor at Amsterdam Transfer Facility- Solid Waste

Description:

Montgomery County
Request for Proposal
Demolition and replacement of concrete floor
1247 State Rte. 5S
Amsterdam, NY 12010

Intent:

It is the intent of this bid proposal to solicit bids for demolition and replacement of a concrete floor at our 1247 State Route 5S, Amsterdam, New York, 12010.

Scope:

Work performed under this bid proposal must include all materials, labor, machinery and permits needed to replace a concrete floor.

Qualifications of Bidder:

When requested by the Commissioner of Public Works, the bidder must present evidence of experience, ability, and financial standing.

Special Conditions:

The bidder is informed that a portion of work described in this RFP must be completed after facility hours of 3:30 P.M. Additionally, all work described must be done solely by the contractor. The contractor will not subcontract for any of the services outlined in the work described.

Mandatory Site Visit:

The bidder is required to set up a date and time with the Montgomery County Commissioner of Public Works before the bid deadline, where they can visit the location of the work to be performed. This will provide them with an opportunity to take their own measurements and be familiar with the space and requested scope of work.

Davis Bacon Act:

The bidder is informed that they are required to follow the Federal Davis Bacon Act, which requires bidders to pay prevailing wage rate and fringe benefits established by the New York State Department of Labor at the time the work is completed. The bidder will be required to submit a certified payroll indicating prevailing wage has been paid before any payment will be released by Montgomery County.

Insurance:

The bidder will be required to submit general liability insurance and Worker's Compensation insurance with limits not less than \$1,000,000.00. All insurance certificates submitted must name Montgomery County, 20 Park Street, Fonda, New York, 12068, as the additional insured.

Work to be performed:

- Demolition and removal of approximately 60 yards of existing concrete floor, approximately 32 x 40, up to 14" thick
- Removal of existing underslab rebar and any underground piping
- Prepare subgrade to receive new 8" minimum thickness concrete floor slab throughout
- New underslab rebar to be a minimum of #5 rebar
- New tip wall curb to be constructed with #5 rebar and poured in place
- Existing condition drawings attached are for reference purposes only and not to be used for design or construction
- New concrete floor slab to have a minimum PSI rating of 5,000 PSI- testing to be performed by a certified laboratory and results submitted to owner.
- Project is to be completed in two phases to maintain daily operations of the transfer facility
- All demolition to be completed during the hours of 3:30 P.M. and 11 P.M., unless otherwise authorized by Montgomery County

All request for proposal must be submitted to Montgomery County Department of Public Works, c/o Purchasing Department, Montgomery County Annex Building, 20 Park Street, Fonda, NY 12068, no later than October 27, 2022, by 1 P.M.